

**work of paving block on both side of the road from mokhadaji circle to gurukul in
u.sardarnagar ward**

SJMMSVY 2025-26		Work No			
N	Description of Items	QTY	Unit	Rate	Amt
1	Earth work in excavation in any soil up to 8 km lead.				
		1548.00	cmt	200.00	309600.00
2	GSB				
		967.50	cmt	999.00	966532.50
3	Rolling & Consolidating				
		3870.00	smt	8.00	30960.00
4	Supply and fitting of 80 mm thick rubber molded paving block				
		3870.00	smt	601.00	2325870.00
5	Supply of manhole				
		15.00	nos	1650.00	24750.00
6	Refitting of manhole / inlet at road level.				
		30.00	nos	1154.00	34620.00
7					
	Pro. Job work for plumbing connection				
		100.00	nos	250.00	25000.00
				Total rs.	3717332.50
				SAY Rs.	3717500.00

નોંધ:- ઉપરોક્ત તમામ ભાવો GST વગરના છે. GST ની રકમ અલગથી ચુકવવામાં આવશે.

